F-4-94

Christian Moser House and Barn

Architectural Survey File

This is the architectural survey file for this MIHP record. The survey file is organized reverse-chronological (that is, with the latest material on top). It contains all MIHP inventory forms, National Register nomination forms, determinations of eligibility (DOE) forms, and accompanying documentation such as photographs and maps.

Users should be aware that additional undigitized material about this property may be found in on-site architectural reports, copies of HABS/HAER or other documentation, drawings, and the "vertical files" at the MHT Library in Crownsville. The vertical files may include newspaper clippings, field notes, draft versions of forms and architectural reports, photographs, maps, and drawings. Researchers who need a thorough understanding of this property should plan to visit the MHT Library as part of their research project; look at the MHT web site (mht.maryland.gov) for details about how to make an appointment.

All material is property of the Maryland Historical Trust.

Last Updated: 11-21-2003

MARYLAND HISTORICAL TRUST DETERMINATION OF ELIGIBILITY FORM

NR Eligible: yes X no

Property Name: Moser Farm and Barn	Inventory Number: F-4-94
Address:	City: south of Thurmont Zip Code:
County: Frederick	USGS Topographic Map:
Owner:	Is the property being evaluated a district? yes
Tax Parcel Number: Tax Map Numbe	
Project:	Agency:
	Date:
Is the property located within a historic district?	
If the property is within a district District	Inventory Number:
NR-listed districtyes Eligible districtyes	Name of District:
Preparer's Recommendation: Contributing resource	yes no Non-contributing but eligible in another context yes
If the property is not within a district (or the property is	a district) Preparer's Recommendation: Eligible X yesno
Criteria: X A B X C D	Considerations: AB C D E FG None
Prepared by: DOT-FHWA Emil Elinsky	Date Prepared: 2/10/1978
Documentation on the property/district is presented in:	
Description of Property and Eligibility Determination:	(Use continuation sheet if necessary and attach map and photo)
Maryland. Essentially unaltered, both structures embody complex enhances the significance of the property since the	of 19th century building traditions in the area of Frederick County, the characteristics of their period. Their survival as a small agrarian he resource also serves as an illustration of the 19th century farmstead in the pattern of agrarian settlement in 19th century Maryland.
MARYLAND HISTORICAL TRUST REVIEW	
	bility not recommended
Criteria: X A B X C D Considerations: MHT Comments	AB C D E F GNone
This property was Federally Nominated for the National I	Register.
Reviewer, Office of Preservation Services	Date
Charles A. Herrington, Keeper	Thursday, March 16, 1978
Reviewer, NR Program	Date

The Christian Moser House and Barn are the remaining historic buildings of a farmstead established about 1830 by Christian Moser. The house and barn are currently unoccupied and used as storage, as a modern residence built in the 1960's is the principal structure on the property. The old house is a two-story log structure on an exposed stone basement with german and clapboard siding which has been removed in some sections, revealing the log walls. Parts of the stone base have also deteriorated, showing the sub-surface portion of the stone wall. The interior of the house has a two-room plan with plaster over lath walls. The roof is covered with corrugated metal. The barn was built about 1870 to replace an earlier barn which burned. It has vertical siding above the original stone foundation. The stall level is enclosed with horizontal flush boards and lath. The house illustrates the vernacular technology of log and stone building of the second quarter of the 19th century through its currently partially deteriorated state.

F-4-94 Christian Moser House and Barn Myersville Frederick County

HISTORIC CONTEXT:

MARYLAND COMPREHENSIVE HISTORIC PRESERVATION PLAN DATA

Geographic Organization: Piedmont (Harford, Baltimore, Carroll, Frederick, Howard, Montgomery Counties, and Baltimore City)

Chronological/Development Period:
Agricultural-Industrial Transition, A.D. 1815-1870

Prehistoric/Historic Period Themes:
Architecture, Landscape Architecture and Community Planning

Resource Type:

Category: Building

Historic Environment: Rural

Historic Function and Use:

Domestic/single dwelling/residence Agriculture/subsistence/animal facility/barn

Known Design Source: None

Maryland Historical Trust State Historic Sites Inventory Form

Survey	No.	F-4-94
--------	-----	--------

Magi No.

DOE __yes __no

1. Nam	e (indicate	preferred name)		
historic Ch	ristian Moser Ho	ouse and Barn		
and/or common				
2. Loca	ation			
street & number	. 1914 Monume	ent Road		not for publication
city, town M	fyersville	_X vicinity of	congressional district	6th
state M	Maryland	county	Frederick	
3. Clas	sification			
Category district _x_ building(s) structure site object	Ownership public private both Public Acquisition in process being considered x not applicab	_x_ yes: restricted ed yes: unrestricted	Present Use agriculture commercial educational entertainment government industrial military	museum park private residence religious scientific transportation x other: not in use
	onard M. and Mary	jorie E. Smith	and mailing addresse	
city, town Mye	ersville	state	e and zip code Md	. 21773
	ation of Le	gal Descripti	on	
courthouse, regi	istry of deeds, etc.	Frederick County Cou	ırthouse	liber ⁴⁴¹
street & number	100 W. Patr	ick Street		folio 572
city, town	Frederick		state	Md. 21701
6. Rep	resentatio	n in Existing	Historical Surv	veys .
title				
date			federal sta	te county local
epository for se	urvey records			
city, town			state	

7. Description

Survey No. F-4-94

Condition Check one Check one excellent deteriorated unaltered x original site good ruins moved moved moved x fair unexposed		
---	--	--

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

CONTRIBUTING RESOURCE COUNT: 2

The Christian Moser House and Barn are the remaining buildings of an agricultural complex established about 1830 by Christian Moser, and consist of a log two-story dwelling in deteriorated condition on an exposed stone foundation and a frame bank barn which appears to have been built during the period 1850-1875. The buildings are located on the northwest side of Monument Road about 1/4 mile west of Interstate 70 near Myersville, Frederick County, Maryland. The buildings are currently used as storage and a modern, non-contributing residence is the principal structure on the current parcel. The house is located about 40 yards west of the modern dwelling facing a pond. The barn is located northwest of the pond.

The Moser House has a three-bay irregular facade on the southeast elevation. The exposed stone foundation has deteriorated and some layers of stone have been removed, with a brick support added at the southeast corner. A recessed six-panel door is located in the center of the basement level, flanked by two 6/6 deteriorated The main first story and the second story have log structure which is revealed under the weathered german siding just above the stone basement and above the first story where a porch was removed prior to 1944, leaving the outline of the The center door has 6 panels with a four-light transom. The flanking windows and the two windows on the second story are 6/6. Some glass is missing or broken in each window. The cornice is boxed and the gable roof is covered with corrugate An interior chimney is located at the west gable end and a later exterior brick chimney rebuilt above an original stone base is at the east end. The east elevation has no openings except at the attic level. The west elevation has two bays with 6/6 sash, some with broken panes. A considerable section of the log structure is revealed on the second story, showing the wood nogging laid between the The gable has clapboard siding which is probably earlier than the main timbers. german siding of the main walls. The northwest elevation is in the best overall condition, with the german siding intact. It has a three-bay irregular arrangement with a 6-panel door set off-center and 6/6 windows, most of which are intact. Louvred shutters flank one second story window. The interior of the house shows a two-room plan with a beaded central partition which has a single opening apparently widened during the mid-20th century. The outside walls are plaster over lath. A corner winding stair is located at the northeast corner of the first floor and a plain fireplace surround opens on the east wall. A sink is located under the window on the southeast wall next to the door. The window and door trim is simply molded and the door has a box lock. The floor is covered with deteriorated linoleum. The second floor was inaccessible.

Barn: The frame bank barn has a stone base and the stall level on the southeast elevation is enclosed with horizontal lath and flush boards. According to Mr. Smith, the current owner, this barn replaced the original barn which burned about 1870. At the time it was rebuilt, undoubtedly on the original stone foundation, it was extended in length. The siding is vertical boards and the roof is covered with corrugated metal. The barn is not currently in use.

1700- _ <u>×</u> _ 1800-	storic -1499 -1599 -1699 -1799 -1899	arche arche arche agrice archite archi	Significance- ology-prehisto ology-historic ulture ecture nerce nunications	ric cc cc ec er ex in	ommunity onservation conomics ducation ogineering ploration	planning on	la n n n	aw terature nilitary nusic hilosophy	,	religion science sculptu social/ humani theater transpo	re tarian rtation
Specific	dates	C. 1830)-1899	Builde	r/Archit	ect					
check:	ar Appl:	nd/or icable Ex	citeria:	AB	c	D					
	Leve.	ı or Sigi	nificance:	natio	naı –	_state	× TOC	d T			
Prepare		a summan	y paragrap	h of sig	nifica	nce and	a gen	eral st	atement	of history	and

F-4-94

Survey No.

8. Significance

The Christian Moser House tells much about the technology of vernacular log building in the second quarter of the 19th century by virtue of its current condition in which sections of the stone foundation have been partially removed and the upper log structure revealed by the removal of deteriorated exterior siding. The interior walls also show how lath and plaster were applied over the log walls. Even the siding suggests how the original clapboards were often replaced on the lower walls with newer german siding after 1850. The house was probably built by Christian Moser about 1830, who is shown on the 1858 Isaac Bond map as the owner in that year (the reprinted Bond map in the vicinity of the Moser House is illegible in photocopy and is not included as an attachment to this form). It was the center of

126-acre farm which remained in the Moser family until 1927. The current owners, one Smiths occupied the log house as their residence from 1944 to the early 1960's. The Moser barn is less important architecturally than the log house, since many barns of the period 1870-1900 are extant in better condition.

9. Major Bibliographical References Survey No. F-4-94

Bond, Isaac. Map of Frederick County, 1858.

Land Records of Frederick County.

Smith, Mr. Leonard M., personal interview, June 9, 1992.

Titus, C.O. Atlas of Frederick County, 1873.

10.	Geo	grap	hica	l Data
-----	-----	------	------	--------

Acreage of nominated property 2 acres Quadrangle name Myersville, Md.	Quadrangle scale1:24000
UTM References do NOT complete UTM references	
Zone Easting Northing	B Zone Easting Northing
c	
E	F
G	H
Verbal boundary description and justification	
Approximately 2 acres including the log house Parcel 35.	and bank barn on Tax Map 37,
List all states and counties for properties overlapping s	state or county boundaries
state code cour	ty code
state code coun	rty code
11. Form Prepared By	
name/title Janet L. Davis, Historic Sites Surve	eyor
organization Frederick County Planning & Zoning	Dept. date July 1992

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to:

Frederick

street & number

city or town

Maryland Historical Trust

Shaw House

12 E. Church Street

21 State Circle

Annapolis, Maryland 21401

(301) 269-2438

MARYLAND HIS UKIOAL TRUST DHCP/DHCE 100 COMMUNITY PLAUL CROWNSVILLE, MD 21032-2023


696-2958

Md. 21701


telephone

state

1914 Monu	generat Rol.		1	4 3		
LIBER/IULIO	GRANTEE	GRANTOR	ORIGINAL TRACTS	COST	DATE	
441/572 31 Mar 44	Leonard M. Smith & Marjonie E. Smith	Drouer F. + annie V. Houne	1400. Tract 1 "Hone fam" 1260. STH 280/ Tract 2 Hearge Hay 130. 326/42	#4000 191 # Lack "		
260/19/ 260/19/ 44 / 1/57/ 14 May 27	Grower & & annie V. Horine	ana Maria Marci		\$ 4,691.25		
1) STH 280/191 26 apro7	ann M. Mason	Lewis Mosee	"Rodenspillers Ramb ley Duabers Tuils "Monpolls" 126 d.	QeL		
2) 326/42 28 Jan 19	Maria Moser	Gleorge E. & Edna F. Houpt	Podensfeller Rambels by Zuakers Dick" Legensmen Lewis Museus Carn	#280		
1) cm 10/159 1 apr 1873	Lewis Moser	Elizabeth Moser eludour of Christian Moser, dec., et al		\$3,424.80		
2) STH 284/247 17 gan 08	Gleorge E. Haupt, Son of Louison of Many ann	Laueson W. + Mary ann Houpt	•			F-4-94
		•			36	
8						



F-4-94 Christian Moser House and Barn Frederick County C.O. Titus, Atlas of Frederick County, 1873.





F- 4-99 Christian Moser House and Bahn Neg- loc. Md. SHPO, Crowisville, Md East elevation 1/5



F. 4-94 Christian Moser Flouse and Barn Frederick County Photo: Janet Cours Nea. loc .: Md. SHPO, Crownsville, Md West elevation



F-4-04 Christian Moser House and Born Frederick County Photo: Jonet Davis Neg. loc. : Md. SHPO, Crownsville, Md. costheost corner view



F-4-94 Ohristian Moser House and Born Frederick County Photo: Jonet Dovis Nea. loc. : Md. SHPO, Crownsville, Md. Interior, general view on first floor 4/5



F-4-94 Christian Moser House and Born Frederick County Photo: Janet Dovis Neg- loc. Ind. SHPO Crownsville Ind Born, northeast elevation